JOHNS RUN EMBAYMENT (OH-20)

1.0 Location

The proposed Johns Run Embayment project area is located in Meigs County, Ohio approximately 6.3 miles south southeast of Racine, Ohio near the small community of Apple Grove, Ohio. The project site is within the Ohio River Racine Pool. The mouth of Johns Run Embayment enters the Ohio River at Ohio River Mile (ORM) 232.2. The project site is within the jurisdiction of the Huntington District, U.S. Army Corps of Engineers (USACE).



2.0 Project Goal, Description, and Rationale

The primary goals of the Johns Run Embayment project are to provide deep water off-channel (slackwater) aquatic habitat that will provide over-wintering habitat for fishes in the Ohio River. Enhanced over-wintering habitat along with increased habitat diversity would improve species diversity, facilitate a sustained fishery resource, and improve the recreational fishery.

Deep water habitat will be created by dredging a channel that is approximately 10-12 feet deep from the mouth of Johns Run at ORM 232.2 to the State Route 338 crossing of Johns Run. The area to be dredged will be a sinuous channel that restores deep water connectivity to the upstream portion of the embayment.

3.0 Existing Conditions

Terrestrial/Riparian Habitat: The banks of Johns Run embayment are populated with a band of riparian trees. The dominant species present in the stand include box elder (*Acer negundo*), black willow (*Salix nigra*), and silver maple (*Acer saccharinum).* To the east of the embayment, there is a commercial sand and gravel operation (Martin Marietta Materials Inc.), and behind the narrow riparian band to the west, the terrestrial habitat is agricultural, predominantly row crops. In the upstream reaches of the embayment to the north, the terrestrial habitat in the Johns Run watershed is predominantly upland forest.

Aquatic Habitats: The Johns Run embayment is a shallow embayment with depths that range from 1-4 feet. The average water depth in the embayment is less than two feet. The banks are characterized by mud, and the bottom substrates are composed primarily of silt, mud, and organic matter. The embayment has become filled with silt primarily from the deposition associated with silt-laden Ohio River waters, especially from flood events. Sediments and debris from the Johns Run watershed may have also contributed to the siltation.

Channel through Johns Run Embayment.

Since this embayment is very shallow with relatively clear water, the habitat conditions are conducive to the production of aquatic macrophytes. Much of the embayment is populated with submersed aquatic plants such as coontail (*Ceratophyllum demersum*), pondweeds (*Potamogeton* spp.), floating seedbox (*Ludwigia peploides*), and others.

Wetlands: The Johns Run embayment is very shallow due to siltation, and a portion of the embayment bottom is exposed annually during the growing season. The mudflats become populated with a variety of wetland plants. The exposed portions of the site produce herbaceous emergent plants such as smartweeds (*Polygonum* spp), rushes (*Juncus* spp.), sedges (*Carex* spp.), flatsedges (*Cyperus* spp.), and cattails (*Typha* spp.). The shallow littoral areas are also populated with a variety of emergent and submergent wetland plants. It is likely that most of the Johns Run embayment, with the exception of the deepest water areas, would be considered jurisdictional.

Emergent wetland vegetation in Johns Run Embayment.

Federally-Listed Threatened and Endangered Species: According to the U.S. Fish and Wildlife Service (USFWS), there is one federally-listed endangered species known to occur in Meigs County, Ohio. The pink mucket pearly mussel (*Lampsilis abrupta*) is a freshwater mussel that was listed as endangered in June 1976 (USFWS, 1998). Although life history information on the pink mucket is unknown, the pink mucket is strictly an Ohioan or Interior Basin species found mainly in the Tennessee, Cumberland, and Ohio River systems. The pink mucket is typically found in medium to large rivers in habitats that range from silt to boulders substrates in water depths that range from 0.5 to 8.0 meters. The species is generally associated with moderate to fast flowing water (USFWS, 1985 and USFWS, 1997). There does not appear to be suitable habitat for this species in the immediate vicinity of the project area.

4.0 Project Diagram



5.0 Engineering Design, Assumptions, and Requirements

5.1 Existing Ecological/Engineering Concern

The Johns Run embayment has filled with sediments due to several factors. These factors include: raised water levels from the impoundment of the Racine Pool; deposition of Ohio River silt-laden waters, especially during flood events; wave action from barge traffic; and headwater sediments from the Johns Run watershed.

5.2 Embayment Dredging

Maintenance dredging of the mouth of the embayment is required to provide deep water connectivity to the remainder of the embayment and to provide a suitable depth for boater access. An estimated 92,500 cubic yards of silty-clay

material would be dredged to restore depths of 9-12 feet in the embayment mouth. A dredge disposal site is adjacent to the embayment, with a natural swale. A small levee, 4.5 feet high and 425 feet in length, would be constructed at the designated disposal site for dewatering.

5.3 Planning/Engineering Assumptions

- A small auger head dredge would be used, and the material would be pumped directly to the disposal site.
- Bottom side slopes will be reshaped to a 3:1.
- All the material required for the levee would be taken from on site.
- A 2,320 gallons per minute (gpm) centrifugal pump would be used for dewatering. Dewatering would commence 18 days after dredging begins to prevent the dewatering basin from exceeding capacity.

6.0 Cost Estimate (Construction)

Dredging - Engineering costs for the proposed project are contained on Table 1. A detailed MCACES cost estimate for the proposed project is included in Appendix C.

Table 1. Engineering Costs.	
Item	**Cost**
Dredging	$116,000
Levee	$1,200
Dewatering	$51,000
Mobilization	$15,200
TOTAL	**$183,400**

7.0 Schedule

Johns Run Embayment Dredging: The estimated construction time for this project is shown on Table 2.

Table 2. Construction Schedule.	
Item	**Time**
Dredging	135 Days
Levee	6 Days
Dewatering	50 Days
Mobilization	4 Days
TOTAL	**195 Days**

8.0 Expected Ecological Benefits

Terrestrial/Riparian Habitat: The impacts of the Johns Run Embayment rehabilitation/dredging project would be primarily in-stream. There would be no reasonably foreseeable beneficial impacts to terrestrial/riparian resources as a result of implementing the proposed project.

Aquatic Habitats: Long-term beneficial impacts to aquatic resources would be anticipated as a result of implementing the proposed project. Dredging of the mouth of Johns Run would result in long-term beneficial impacts to fishes due to the improved/deepened access to the Johns Run embayment. Fishes would be allowed free access to the embayment, especially during low flow periods. Habitat requirements for fishes change seasonally and improved access to the

embayment would be considered beneficial. Restoring/increasing the depths of the embayment would provide over-wintering habitat for fishes, especially sport fish such as black basses.

Wetlands: There would be no beneficial impacts to jurisdictional wetlands as a result of implementing the proposed project.

Federally-Listed Threatened and Endangered Species: There would be no reasonably foreseeable beneficial impacts to federally-listed threatened or endangered species as a result of implementing the proposed project.

Socioeconomic Resources: There would be short-term and long-term beneficial impacts to socioeconomic resources as a result of implementing the proposed project. The short-term beneficial impacts would be related to costs and local expenditures associated with the construction/dredging of the embayment. Long-term socioeconomic benefits would be realized through improved recreational fishing opportunities. Long-term indirect beneficial impacts will be realized through local expenditures for fishing tackle, hunting and fishing gear, food, gas, and other associated needs.

9.0 Potential Adverse Environmental Impacts

Terrestrial/Riparian Habitat: There would be short-term adverse impacts to terrestrial/riparian resources as a result of implementing the proposed project. There would be short-term adverse impacts to terrestrial species from construction-related noise and disturbance. Considering the existing high volume of disturbance from the adjacent sand/gravel operation, barge traffic along the Ohio River and recreational boat usage in the area, it is likely that the increased noise/disturbance impacts would be very minor. There would be short-term adverse impacts to the agricultural lands that lie to the west of the embayment. This area would serve as the dredge disposal site. Adverse impacts to this area would be considered short term, because it is assumed that the site can be farmed following the dewatering and grading of the spoil material.

Aquatic Habitats: There would be a potential for adverse affects to aquatic species, especially immobile benthic invertebrates and young-of-the-year fishes during the dredging of the Johns Run embayment. Localized populations of benthic invertebrates could be directly disturbed during the construction operation. In addition, sensitive aquatic species immediately downstream from the site could be adversely impacted by degraded water quality associated with displaced sediments, however these adverse impacts to aquatic species would be short term.

The shallow water and vegetated habitats in Johns Run embayment provide cover, spawning habitat, and nursery habitat for fishes. The structure associated with emergent and submersed vegetation provides habitat for aquatic invertebrates and cover for fishes, especially young-of-the-year (Wege, 1979; Killgore, 1989; and Eggering, 1991). The loss of littoral and submersed aquatic vegetative habitats would be considered adverse for invertebrates and some fishes, especially young-of-the-year. Considering the overall size of the embayment compared the actual amount of dredging envisioned, these impacts would not be severe.

Wetlands: There would be long-term adverse impacts to jurisdictional wetlands as a result of implementing the proposed project. A portion of the herbaceous emergent wetlands that populate the mudflats in the bottom of the Johns Run embayment would be removed during the dredging operation. Adverse impacts to jurisdictional wetlands could be minimized by restricting the dredging to the existing Johns Run creek-channel, which would leave most of the exposed mudflat intact.

Federally-Listed Threatened and Endangered Species: There would be a very slight potential for adverse effects to the pink mucket pearly mussel during the dredging of the Johns Run embayment. Mussels immediately downstream from the construction/dredge site could be adversely impacted by perturbed water quality conditions associated with displaced sediments. Since the pink mucket pearly mussel needs moderate to fast flowing water (USFWS, 1985 and USFWS, 1997) and since the Johns Run embayment is considered a slackwater habitat with a silt/muck bottom, it is highly unlikely that this species is found in the embayment.

Socioeconomic Resources: There would be no reasonably foreseeable adverse socioeconomic impacts as a result of implementing the proposed project.

10.0 Mitigation

Adverse impacts to jurisdictional wetlands could be minimized by restricting dredging to the existing Johns Run creek-channel, which would leave most of the exposed mudflat intact. It is likely that the removal/destruction of jurisdictional wetlands would require in-kind mitigation.

Minor impacts associated with site dredging and spoil placement may occur during the construction of this project, however, no significant adverse impacts are expected. The use of best management practices and proper construction techniques would minimize adverse water quality impacts.

11.0 Preliminary Operation and Maintenance Costs:

Maintenance Dredging Operation and Maintenance costs are summarized on Table 3.

Table 3. Operation and Maintenance Costs

Maintenance	Frequency	Costs
Maintenance Dredging	25 years	$36,700

12.0 Potential Cost Share Sponsor(s)

- State of Ohio
- barge/towing industry

13.0 Expected Life of the Project

It is anticipated that the dredging operation would provide meaningful depths for fishes for approximately 25-30 years before additional dredging would be necessary.

14.0 Hazardous, Toxic, and Radiological Waste Considerations

Potential impacts of hazardous, toxic, and radiological waste (HTRW) at the site were visually assessed during a site visit.

Site Inspection Findings. The project site is located near the mouth of Johns Run at Ohio River mile 232.2 in Meigs County, Ohio. The nearest towns are Apple Grove, Ohio and Millwood, West Virginia.

The following environmental conditions were considered when conducting the June 8, 1999 project area inspection:

- Suspicious/Unusual Odors;
- Discolored Soil;
- Distressed Vegetation;
- Dirt/Debris Mounds;
- Ground Depressions;
- Oil Staining;
- Above Ground Storage Tanks (ASTs);
- Underground Storage Tanks (USTs);
- Landfills/Wastepiles;
- Impoundments/Lagoons;
- Drum/Container Storage;
- Electrical Transformers;
- Standpipes/Vent pipes;

- Surface Water Discharges;
- Power or Pipelines;
- Mining/Logging; and
- Other

An unfinished pier is in the project area. A sand/gravel bar is to the east and areas of wetland, riparian and forest habitat is to the north of the project area. None of the environmental conditions listed above were observed in the project area.

15.0 Property Ownership & River Access

Selected data on properties immediately adjacent to the concept site were collected from the county courthouse for each site. Data collected included map and parcel identification number, property owner's name and mailing address, acreage of the potentially affected parcel, and market value of the parcel. This procedure involved obtaining a plat or parcel map of the site and surrounding area which identified each parcel with a corresponding map and parcel number. The map\parcel identification number was subsequently used to determine the property owner's name and mailing address from records in the County Assessor's or County Auditor's office.

The market value of each parcel as contained in the property tables reflects the assessed valuation to supposedly market value ratio used by the State for taxation purposes. These assessed values reflect 1998 assessments. The assessed valuation ratio is 35 percent for Ohio.

The above ratio was used to approximate the market value of each property. However, the resultant market value calculated under the above procedure may be below the actual value of the land in the real market. Local real estate brokers could provide a more accurate estimate of actual land values.

The collected property data indicate that private agricultural and commercial land is adjacent to Johns Run embayment. Dredging equipment for the project can access Johns Run from the Ohio River. Dredge disposal is proposed to occur on adjacent agricultural lands. Access to these lands will be required for the proposed project (See Table 4).

Table 4. Property Characteristics

Site Name: John's Run
Location: Meigs County, Ohio

Map/Parcel Number	Owner	Mailing Address	Market Value	Acreage
05/011-001	Martin Marietta Materials, Inc.	2710 Wycliff Road Raleigh, North Carolina 27607	$112,343	100 .00
05/011-002	Richards & Sons, Inc.	49947 SR 338 Racine, Ohio 45771	$20,828	100.00
05/011-003	Richards & Sons, Inc.	49947 SR 338 Racine, Ohio 45771	$219,143	100.00
05/011-004	Richards & Sons, Inc.	49947 SR 338 Racine, Ohio 45771	$108,142	99.09

* Denotes improvements on property.

16.0 References

References:	
Eggering, 1991	Eggering, L. F. 1991. Thesis: The affect of aquatic macrophytes on the available prey/predator ratio of fishes in the littoral area of Kentucky Reservoir. Murray State University, Murray, Kentucky.
Killgore, 1989	Killgore, K. J., R. P. Morgan II, and N. B. Rybicki. 1989. Distribution and abundance of fishes asociated with submersed aquatic plants in the Potomac River. North American Journal of Fisheries Management.
USFWS, 1985	U.S. Fish and Wildlife Service, 1996. Recovery plan for the pink mucket pearly mussel. Atlanta, Georgia.
USFWS, 1997	U.S. Fish and Wildlife Service, 1997. Species Accounts: pink mucket pearly mussel (*Lampsilis abrupta*).
USFWS, 1999	U.S. Fish and Wildlife Service, July 8, 1998. Federally Endangered, Threatened and Proposed Species, Ohio.
Wege, 1979	Wege, G. J. and R. O. Anderson. 1979. Influence of artificial structures on largemouth bass and bluegills in small ponds. North Central Division American Fisheries Society Special Publication 6.

APPENDIX A Threatened & Endangered Species

APPENDIX B Plan Formulation and Incremental Analysis Checklist

Project Site Location:

The proposed Johns Run Embayment project area is located in Meigs County, Ohio approximately 6.3 miles south southeast of Racine, Ohio near the small community of Apple Grove, Ohio. The project site is adjacent to the Ohio River Racine Pool, and the mouth of the Johns Run Embayment enters the Ohio River at Ohio River Mile (ORM) 232.2. The project site is within the jurisdiction of the Huntington District, U.S. Army Corps of Engineers (USACE).

Description of Plan Selected:

The primary goals of the Johns Run Embayment project are to provide deep water off-channel (slackwater) aquatic habitat that will provide over-wintering habitat for fishes in the Ohio River. Enhanced over-wintering habitat couple with increased habitat diversity would correlate with a sustained fishery resource and an improved recreational fishery.

Deep water habitat will be created by dredging a channel that is approximately 10-12 feet deep from the mouth of Johns Run at ORM 232.2 to the State Route 338 crossing of Johns Run. The area to be dredged will be a sinuous channel that restores deep water connectivity to the upstream portion of the embayment.

Alternatives of the Selected Plan:

Smaller Size Plans Possible? Yes and description

Reduce the amount of dredging.

Larger Size Plan Possible? Yes and description

Increase the amount of dredging.

Other alternatives? No

Restore/Enhance/Protect Terrestrial Habitats? [ ] **Objective numbers met** [ ]

Restore, Enhance, & Protect Wetlands? [ ] **Objective numbers met** [ ]

Restore/Enhance/Protect Aquatic Habitats? [Yes] **Objective numbers met** [A1, A5, A6]

Type species benefited: Fishes (especially black basses) and invertebrates including mussels.
Endangered species benefited: No

Can estimated amount of habitat units be determined: ? acres deepened by dredging

Plan acceptable to Resources Agencies?
U.S. Fish & Wildlife Service?
State Department of Natural Resources? Yes – Ohio DNR

Plan considered complete? **Connected to other plans for restoration?**

Real Estate owned by State Agency? **Federal Agency?**
Real Estate privately owned? Some adjacent lands are privately owned.
If privately owned, what is status of future acquisition Acquisition is not necessary.

Does this plan contribute significantly to the ecosystem structure or function requiring restoration? What goal or values does it meet in the Ecosystem Restoration Plan?

Provide habitat diversity, over-wintering habitat, and winter velocity shelters for fishes.

Is this restoration plan a part of restoration projects planned by other agencies? (i.e. North American Waterfowl Management Plan, etc.)

No

In agencies opinion is the plan the most cost effective plan that can be implemented at this location?

Can this plan be implemented more cost effectively by another agency or institution?
Yes / No
Who:

From an incremental cost basis are there any features in this plan that would make the project more expensive than a typical project of the same nature? For embayment type plans is there excessive haul distance to disposal site? More expensive type disposal? Spoil that requires special handling/disposal?

Potential Project Sponsor:

Government Entity:_____
Non-government Entity _____

Corps Contractor _____Date_____

U.S. Fish & Wildlife Representative _____Date_____

State Agency Representative _____Date _____

U.S. Army Corps of Engineers Representative _____Date _____

Terrestrial Habitat Objectives

T1 Riparian Corridors

T2 Islands

T3 Floodplains

T4 Other unique habitats (canebrakes, river bluffs, etc.)

Wetland Habitat Objectives

W1 Forested Wetlands: Bottomland Hardwoods

W2 Forested Wetlands: Cypress/Tupelo Swamps and other unique forested wetlands

W3 Scrub/Shrub Emergent Wetlands: isolated from the river except during high water and contiguous (includes scrub/shrub wetlands in embayments and island sloughs)

Aquatic Habitat Objectives

A1 Backwaters (sloughs, embayments, oxbows, bayous, etc.)

A2 Riverine submerged and aquatic vegetation

A3 Sand and gravel bars

A4 Riffles/Runs (tailwaters)

A5 Pools (deep water, slow velocity, soft substrate)

A6 Side Channel/Back Channel Habitat

A7 Fish Passage

A8 Riparian Enhancement/Protection

APPENDIX C Micro Computer-Aided Cost Engineering System (MCACES)

Tue 24 Aug 1999 U.S. Army Corps of Engineers
TIME 08:40:08
Eff. Date 08/23/99 PROJECT ORMSSE: ORMSS - Environmental Enhancement
John's Run Embayment
TITLE PAGE 1

ORMSS - Environmental Enhancement

Designed By: LE, RH, TW
Estimated By: Todd Williams

Prepared By: Todd Williams

Preparation Date: 08/23/99
Effective Date of Pricing: 08/23/99

Sales Tax: 6.00%

M C A C E S G O L D E D I T I O N

Release 5.30

LABOR ID: ORMSSE EQUIP ID: RG295A Currency in DOLLARS
CREW ID: NAT95A UPB ID: UP99EA

```
Tue 24 Aug 1999                                   U.S. Army Corps of Engineers
TIME 08:40:08
Eff. Date  08/23/99                  PROJECT ORMSSE:   ORMSS - Environmental
Enhancement
                                                        John's Run Embayment
SETTINGS PAGE    1
                                                    04-07. John's Run Embayment
                                                        ** LINK LISTING **
-------------------------------------------------------------------------------
-------------------------------------------------
04-07. John's Run Embayment              REFERENCE        REF VALUE
OPERATOR         LOCAL INPUT        QUANTITY UOM
-------------------------------------------------------------------------------
-------------------------------------------------

04-07 John's Run Embayment

1.0000 LS


04-07{0603 Fish & Wildlife Facilities and

1.0000 LS

04-07{060373 Habitat & Feeding Facilities

1.0000 LS

04-07{060373}001 Mobilization
                                        D                   0.0000 LS
1.0000          0.0000 LS


04-07{060373}002 Dredging

92500.0000 CY
                                     PRODUCTIVITY         90.0000 CY /
                                     DURATION           1027.7778


0100    AUGERHD MUDCAT, 8" DISCHARGE DIA D               1027.7778     *
Multiply by           1.0000       1027.7778 HR
0200    Outside Laborer                 D                1027.7778     *
Multiply by           2.0000       2055.5556 HR
0300    Outside Equip. Op. Medium       D                1027.7778     *
Multiply by           1.0000       1027.7778 HR

04-07{060373}003 Levee

1310.4200 CY
                                     PRODUCTIVITY         90.0000 CY /
                                     DURATION             14.5602


0100    Excavation                      P                1310.4200 CY  *
Multiply by           1.0000       1310.4200 CY
0200    Embankment                      P                1310.4200 CY  *
Multiply by           1.0000       1310.4200 CY
```

```
0300    Compaction                          P                1310.4200 CY  *
Multiply by           1.0000       1310.4200 CY

04-07{060373}004 Dewatering

43592727.0000 GAL
                                       PRODUCTIVITY          90.0000 GAL/
                                       DURATION           484363.6333


0200    Outside Equip. Oper Light          A 0100           1329.0000 HR  *
Multiply by           1.0000       1329.0000 HR
0300    Outside Laborer                    A 0100           1329.0000 HR  *
Multiply by           0.2500        332.2500 HR

LABOR ID: ORMSSE    EQUIP ID: RG295A                 Currency in DOLLARS
CREW ID: NAT95A   UPB ID: UP99EA
```

Tue 24 Aug 1999 U.S. Army Corps of Engineers
TIME 08:40:08
Eff. Date 08/23/99 PROJECT ORMSSE: ORMSS - Environmental Enhancement
DETAILED ESTIMATE John's Run Embayment
DETAIL PAGE 1
04. Ohio

John's Run Embayment	QUANTY	UOM	CREW ID	OUTPUT	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT
Ohio										
John's Run Embayment										
Study Level: Concept										
Project Goals:										
Dredge mouth of embayment to reestablish depths of 9-12'.										
Fish & Wildlife Facilities and Sanctuary										
Habitat & Feeding Facilities										
Mobilization										
Dredge	2.00	LS		0.00	5,800	8,700	0	0	14,500	7250.00
Bull Dozer	2.00	LS		0.00	59	304	0	0	363	181.50
Vibrating Roller	2.00	LS		0.00	59	304	0	0	363	181.50
Mobilization					5,918	9,308	0	0	15,226	
Dredging										
AUGERHD MUDCAT, 8" DISCHARG	1027.78	HR	M10EL007	1.00	0	48,351	0	0	48,351	47.04
Outside Laborer	2055.56	HR	X-LABORER	1.00	46,884	0	0	0	46,884	22.81
Outside Equip. Op. Medium	1027.78	HR	X-EQOPRMED	1.00	20,815	0	0	0	20,815	20.25
Dredging	92500	CY			67,699	48,351	0	0	116,050	1.25

```
                    Levee
 Excavation                    1310.42 CY  CODTR       410.00          496
118           0           0          614    0.47
 Embankment                    1310.42 CY  CODTR       600.00          339
81            0           0          420    0.32
 Compaction                    1310.42 CY  COFCA      1900.00           98
6             0           0          104    0.08
 6" lifts, 4 passes
                                                                ----------- ------
----- ----------- ----------- -----------
 Levee                         1310.42 CY                              934
205           0           0        1,138    0.87


                    Dewatering
 PUMP,CENTRF,DW,8"D,2320GPM/ 1329.00 HR  P60ML005      1.00            0
11,632           0           0       11,632    8.75
 20'HD
 Assume 2000 gallons of water
 per cubic yard of material
 Outside Equip. Oper Light   1329.00 HR  X-EQOPRLT     1.00       31,830
0             0           0       31,830   23.95
 Outside Laborer              332.25 HR  X-LABORER     1.00        7,578
0             0           0        7,578   22.81



LABOR ID: ORMSSE    EQUIP ID: RG295A                  Currency in DOLLARS
CREW ID: NAT95A   UPB ID: UP99EA
```

Tue 24 Aug 1999 U.S. Army Corps of Engineers
TIME 08:40:08
Eff. Date 08/23/99 PROJECT ORMSSE: ORMSS - Environmental Enhancement
DETAILED ESTIMATE John's Run Embayment
DETAIL PAGE 2
04. Ohio

John's Run Embayment	QUANTY	UOM	CREW ID	OUTPUT	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT
Dewatering	43592727	GAL			39,408	11,632	0	0	51,040	0.00
Habitat & Feeding Facilitie					113,958	69,496	0	0	183,454	
Fish & Wildlife Facilities					113,958	69,496	0	0	183,454	
John's Run Embayment					113,958	69,496	0	0	183,454	

LABOR ID: ORMSSE EQUIP ID: RG295A Currency in DOLLARS
CREW ID: NAT95A UPB ID: UP99EA

Tue 24 Aug 1999 U.S. Army Corps of Engineers
TIME 08:40:08
Eff. Date 08/23/99 PROJECT ORMSSE: ORMSS - Environmental Enhancement
ERROR REPORT John's Run Embayment
ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

LABOR ID: ORMSSE EQUIP ID: RG295A Currency in DOLLARS
CREW ID: NAT95A UPB ID: UP99EA

Tue 24 Aug 1999 U.S. Army Corps of Engineers
TIME 08:40:08
Eff. Date 08/23/99 PROJECT ORMSSE: ORMSS - Environmental Enhancement
TABLE OF CONTENTS John's Run Embayment
CONTENTS PAGE 1

No Summary Reports...

DETAILED ESTIMATE

DETAIL PAGE

07. John's Run Embayment
0603. Fish & Wildlife Facilities and
73. Habitat & Feeding Facilities

No Backup Reports...

* * * END TABLE OF CONTENTS * * *